KOLAR DIVISION.

ADVERTISEMENT.

The 30th December 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 15th January 1888, for restoring Hadrani Tank, Registered No. 29 of Sidlaghatta Taluk. An approximate estimate of quantities is given below. These quantities, are not guaranteed. The work should be completed by the end of March 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes as earnest money, and be superscribed "Tender for restoring Hadrani Tank, Registered No. 29 of Sidlaghatta Taluk": in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Bund.

Earthwork	C. Yd.	9,400
Old stone work	"	1,200
New stone work	"	3,800
Gauge stone	No.	1
Grade stones	"	41
Repairing left sluice ..	L. sum.	
Sluices in dam wall of waste weirs	No.	2

Right Kodi.

Brick masonry	C. Ft.	10,150
Chunam plastering ..	Sq.	2,850
Old sujikat	C. Ft.	318
Stone slabs, 9" thick ..	S. Ft.	920
Do for coping 6" thick ..	S. Ft.	374
Concrete	C. Ft.	748
Stone revetment	C. Yd.	31
Excavation	C. Yd.	420

Left Kodi.

Brick masonry	C. Ft.	14,650
Chunam plastering ..	Sq.	3,700
Old sujikat	C. Yd.	416
Stone slabs, 9" thick ..		1,200
Do for coping 6" thick ..		488
Concrete	C. Ft.	975
Stone revetment	C. Yd.	31
Excavation	C. Yd.	612

Left bank channel.

Earthwork	C. Yd.	21,780
Cattle bridges	No.	6
MacAvoys	"	30
Mile stones	"	4
Furlong stones		2
Grade stones	"	72
Boundary stones	"	108
Cross drainages	R. Ft.	300

Right bank channel.

Earthwork	C. Yd.	24,200
Cattle bridges	No.	8
MacAvoys	"	40
Mile stones	"	5
Furlong stones	"	35
Grade stones	"	80
Boundary stones	"	120
Cross drainages	R. Ft.	250

Y. SRINIVASA RAO,
Executive Engineer.

VACCINE DEPARTMENT.

The 28th December 1887.

The Deputy Inspector of Vaccination, Shimoga District, will visit the following hoblis of the Shimoga Taluk from the 1st week of January 1888 till his other movements are notified:—

1. Shimoga Hobli. 2. Bidrur Hobli in order.

for the purpose of inspecting the work done by the vaccinator, and will, with the vaccinator, vaccinate all who are willing to undergo the vaccine operation.

D. A. CHORSI,
Civil Surgeon, Shimoga District.